The 4th International Symposium – Supercritical CO₂ Power Cycles Technologies for Transformational Energy Conversion September 9-10, 2014, Pittsburgh, Pennsylvania

Supercritical Carbon Dioxide Power Cycle Development Overview Kenneth J Kimball BMPC, Knolls Atomic Power Laboratory

P.O. Box 1072, Schenectady, NY 12301-1072

Ken Kimball has been actively involved with supercritical CO2 Brayton power cycle development since 2005 working at the Knolls Atomic Power Laboratory in Schenectady, NY, USA. This effort has included working closely with numerous University, National Laboratory and Industry groups. He has a BS degree in mechanical engineering from Worcester Polytechnic Institute and an MS degree in mechanical engineering from Rensselaer Polytechnic Institute. He has previously presented development progress at the Supercritical CO2 Brayton power cycle development symposiums in 2009 and 2011 and the ASME Turbo Conferences in 2012 and 2013.

Abstract

Bechtel Marine Propulsion Corporation (BMPC) is testing a supercritical carbon dioxide (S-CO₂) Brayton system at the Bettis Atomic Power Laboratory. The 100 kWe Integrated System Test (IST) is a two shaft recuperated closed Brayton cycle with a variable speed turbine driven compressor and a constant speed turbine driven generator using S-CO₂ as the working fluid. The IST was designed to demonstrate operational, control and performance characteristics of an S-CO₂ Brayton power cycle over a wide range of conditions. The IST design includes a comprehensive instrumentation and control system to facilitate precise control of loop operations and to allow detailed evaluation of component and system performance. A detailed dynamic performance model is being used to predict IST performance, support test procedure development and to evaluate test results. An overview of IST testing progress and plans is provided. Testing in the IST was initiated in 2012. Test operations to date included successful system startup, initial transition to electrical power generation, increased power operations and transition to load control testing using independent speed control of the turbo-machinery. Results of testing completed to date and future testing plans will be summarized.



Bechtel Marine Propulsion Corporation Knolls Atomic Power Laboratory Schenectady, NY Bettis Atomic Power Laboratory West Mifflin, PA

Supercritical Carbon Dioxide Power Cycle Development Overview

KJ Kimball Bechtel Marine Propulsion Corporation September 10, 2014

BMPC Development Program Overview:

- S-CO₂ Brayton Cycle Integrated Systems Test (IST)
 - Turbo-machinery (turbine, compressor, bearings, seals)
 - Control system (startup, power control)
 - Heat exchangers (shell and tube)
 - Practical considerations (mass control, instrumentation, system leakage)
- Compact Heat Exchanger Development
 - High pressure, compact, fatigue resistant, affordable
- MW scale development vision
 - Based on kW development
 - Scale-up issues
 - Transition from experimental to demonstration stage



Bechtel Marine Propulsion Corporation Knolls Atomic Power Laboratory Schenectady, NY Bettis Atomic Power Laboratory West Mifflin, PA

S-CO₂ Integrated System Testing

IST Physical Layout



IST Turbomachinery





Thrust Bearing





Compressor/Diffuser



Turbine

Maximum Power Operation

November 2013 – 40kWe





Compressor Map



Power Increase Transient

- Initial Conditions: Hot Idle (540°F/37,500 rpm)
- TG speed increased
- TC speed increased in steps
- Compressor recirculation valve decreased in steps
- Water flow automatically controlled to maintain compressor inlet T



Supercritical CO₂ Power Cycles Symposium September 9-10, 2014

Power Increase Transient: Heat Exchanger Heat Duties





IHX Heat Transfer





Precooler Heat Transfer



🕮 Practical Aspects of Supercritical Carbon Dioxide Brayton System Testing

E. M. Clementoni & T. L. Cox, Bechtel Marine Propulsion Corporation



Design Considerations

- Off-design/transient model valuable for startup & low power operation
- Good experience with Grayloc & Swagelok fittings and ANSI flanges
- Thermal stresses need considered early for compact arrangement

Loop Cleanliness

- S-CO₂ is a great solvent
- Material quality and cleanliness controls are important
- EPDM acceptable, Viton and Teflon tape problematic
- Turbine nozzle erosion believed to be caused by debris in system

Operational Experience

- 100 kWe Integrated System Test
- Shakedown started Fall 2011
- Over 165 hours of Brayton system operation
- Achieved 40% of design power





System Fill and Leakage

- IST uses Coleman Instrument grade (99.99%) CO₂ for fill
- Three cycles of pulling vacuum and filling to atmospheric pressure before full fill
- Low leakage levels from valve stem packing and large shaft seals

Instrumentation

- Marlin Type T SLE thermocouples
- Rosemount pressure transducers
- MicroMotion Elite Coriolis meters
- REFPROP calculated density (T&P) agrees well with measured density

IST with Recompression Cycle Control Features



This loop design shows how recompression control features could be placed in the IST, allowing loop hydraulic control for startup, heatup and low power operation.

IST Up-Power Maneuver in Recompression Configuration

Using end states that have been optimized for adequate surge margin this up-power transient shows good performance, with minimal under/over shoot.



Up-power rates >1%/s would be possible for a well designed recompression loop.



Bechtel Marine Propulsion Corporation Knolls Atomic Power Laboratory Schenectady, NY Bettis Atomic Power Laboratory West Mifflin, PA

S-CO₂ Heat Exchanger Development

Heat Exchanger Testing



River Water Cooling

Testing Conditions:

Heat Input/Rejection 20-90 kW_t Pressure: ≈1,200-1,500 psi Temperature: ≈300-500°F Flow rate: ≈2-3 lbm/second



Supercritical CO₂ Power Cycles Symposium September 9-10, 2014

2" to 10" sched 160 Pipe (316 SS)

Recuperator Designs Tested

WavyFin



 β =3,300-4,500 m²/m³





 β =7,000-8,000 m²/m³







Folded Wavy-Fin Results







Prototype demonstrated thermalhydraulic performance.



Bechtel Marine Propulsion Corporation Knolls Atomic Power Laboratory Schenectady, NY Bettis Atomic Power Laboratory West Mifflin, PA

Summary of Progress to Date

S-CO₂ Integrated System Testing

- IST demonstrating controllability of a two shaft simple S-CO2 Brayton cycle
- Normal power operation over range of power levels up to ~50 kWe has commenced
- TRACE transient modeling:
 - Validation has commenced
 - Approaching real time execution
 - Demonstrates controllability of re-compression cycle

S-CO₂ Heat Exchanger Development

- IST heat exchangers meeting expectations and validating performance models
- More compact/fatigue resistant heat exchangers being designed, fabricated and tested in dedicated 300kW test facility



Bechtel Marine Propulsion Corporation Knolls Atomic Power Laboratory Schenectady, NY Bettis Atomic Power Laboratory West Mifflin, PA

MW Scale Development

S-CO₂ Power Cycle Development Approach



Path to S-CO₂ Power Cycle Commercial Implementation



Supercritical CO₂ Power Cycles Symposium September 9-10, 2014

Development

Technology