

Simulation of IST Turbomachinery Power-Neutral Tests with the ANL Plant Dynamics Code

Anton Moiseyev and Jim Sienicki
Argonne National Laboratory, USA

The 6th International Symposium - Supercritical CO₂ Power Cycles
Pittsburgh, PA
March 27-29, 2018


ANL Plant Dynamics Code (PDC)

- **Specifically developed for analysis of sCO₂ cycles**
 - One-dimensional system level transient analysis code
 - Targets the specific features of the cycle
 - Operation close to the critical point
 - Recompression cycle (if needed)
 - Real CO₂ properties
 - Property variations in HX's and turbomachinery
 - No simplifying ideal gas assumptions
 - Compressibility effects
- **Incorporates sCO₂ cycle control mechanisms and logic**
- **Incorporates steady-state design code to determine cycle initial conditions**
- **Design and performance subroutines for both turbine and compressor**
- **This presentation describes validation work with Naval Nuclear Laboratory IST data**




Naval Nuclear Laboratory's Integrated System Test

- ≈ 1 MWt heat input through oil-to-CO₂ HX
- Simple (not recompression) cycle configuration, one recuperator
- Two turbines, one drives compressor
- Turbomachinery leakage collection system




Simulated Tests

- First PDC validation results with IST data were reported at the 5th sCO₂ Symposium in San Antonio in 2016
- Recently, new IST test data was provided to ANL
 - Same test configuration and equipment
- **Power-neutral operation** of the turbine-compressor unit
 - No power in alternator
 - TAC is free to change speed
 - Speed is controlled by Recirculation Valve
- **Benefits for PDC validation**
 - Shaft dynamics
 - Equivalent to turbine bypass control and compressor surge control



Test 64661: Compressor-Inlet Temperature Sensitivity

- CIT was commanded to change
 - By means of water flow control
- Turbine-Compressor speed of 48,675 rpm is requested
 - Controlled by CR valve
- Test duration: 5,500 seconds (1.5 hours)
- All other inputs are basically fixed
 - Turbine-Generator speed, Turbine-inlet temperature, oil flow rate
 - No turbine bypass or throttling
- Expected outcome: Lower CIT -> Decreased compressor work -> TC tends to increase speed -> Need to open CRv to maintain speed



PDC Simulation of Test 64661

■ Three stages

1. Steady-state for conditions prior to the test

- Good agreement, except:
- Larger than before discrepancy in flow split between turbines
- Attributed to the recent change in turbine materials, which might affect clearances at operation

2. Transient with given TC speed and CR valve position

- Same mode as previous PDC simulation of IST tests
- To validate cycle response

3. Full simulation with TC speed control

- To validate the shaft speed control






PDC Simulation of Test 64661: Transient





- **First transient results showed much slower cooler response in PDC**
 - Resulting in much larger oscillations of water flow rate
- **Error in the shell-and-tube heat exchanger tube mass was discovered and corrected**
 - Both SNL RCBC and all recent sCO₂ control analysis used PCHE
 - Shell-and-tube HX tube mass error neither affected those results nor could be identified from previous validation

PDC Simulation of Test 64661: Full Transient





- PDC maintains TC speed
 - Even better than the actual test
 - Not including dead bands, electronic delays, etc.
- Very good agreement on the CRv position



PDC Simulation of Test 64661: Full Transient





PDC Simulation of Test 64661: Full Transient



Test 65261-P: Varying Power Test

- **TC speed was commanded to change**
 - Between 42,000 and 52,000 rpm
- **Corresponds to pre-calculated TG power**
 - Between 5% and 35%
 - Higher TC speeds increases CO₂ flow rate in TG
- **Test duration: 4,600 seconds (1.3 hours)**
- **All other inputs are basically fixed**
 - TG speed, Turbine-inlet temperature, compressor-inlet temperature, oil flow rate
 - No turbine bypass or throttling





PDC Simulation of Test 65261-P





- Same three stages
 1. Steady-state for conditions prior to the test
 2. Transient with given TC speed and CR valve position
 3. Full simulation with TC speed control
- Level of agreement for Steady-state and Stage 2 are similar to the Test 64661
 - Largest discrepancies are generator turbine outlet temperature and flow split between the turbines

PDC Simulation of Test 65261-P : Full Transient





- PDC matches TC speed
 - Validates control setup
- Predicted CRv position progressively deviates from test data, as speed increases
 - Issue with scaling shaft windage losses with speed only
 - Neglecting cavity pressure and fluid density effect (not modeled)



PDC Simulation of Test 65261-P : Full Transient



PDC Simulation of Test 65261-P: Full Transient



Summary

- **Validation of PDC for sCO₂ cycle has been continued**
 - With new test data from IST
 - Test 64661: Compressor-Inlet Temperature Sensitivity
 - Test 65261-P: Varying Power Test
- **Power-neutral operation of turbine-compressor shaft**
 - No external power or control from alternator
 - Shaft speed is determined from shaft power balance
 - Speed controlled by compressor recirculation valve
- **New test data is important for PDC validation**
 - Allows validation of the shaft dynamics equations in asynchronous mode
 - Shaft speed control with the CR valve allows for testing the code control logic
 - Also serves as a good test for validation of both the compressor surge control and the turbine bypass control actions
 - Varying compressor-inlet temperature change test allows validation of the transient response of the precooler

Summary

- **New test data was obtained in the same loop configuration and the same equipment as the previous data analyzed**
 - No changes to the PDC input (except for transient definitions)
 - However, the turbomachinery equipment was rebuilt several times
 - Including a material change
 - Possible effect on the clearances
- **PDC simulation was done in three stages**
 - Steady-state
 - Good agreement, except generator turbine performance
 - Transient with given TC speed and CRv position
 - Same as previous work
 - Helped to identify an error with shell-and-tube HX tube mass
 - Full transient with active control
 - Validates control setup and shaft speed equations
 - Both test results show good agreement
 - TC shaft power balance affected by windage losses approximation

