



Supercritical CO₂ Turbomachinery Configuration and Controls for a Zero Emission Coal Fired Power Plant: System Off Design & Control of System Transients

Chandrashekhar Sonwane, David Hanks, Tony Eastland,
Ken Tran, Marinelle Peneda, Jeff Mays, and John Vega


September 9-10, 2014

Introduction/Background

- **SCO₂ Recompression Brayton cycle efficiencies have been analytically shown to be very attractive**
 - Relative to an atmospheric oxy-fired supercritical steam pulverized coal plant with carbon capture
- **Previous phase defined a reference plant with a fossil heat source and identified development needs**
 - Study completed for Leonardo Technologies, Incorporated (LTI)
- **Objective of this effort was to analyze transient operation and identify any additional development needs**
 - Start-up
 - Shut-down
 - Partial load operation


Reference Fossil Fueled Plant

- **550 MWe with Oxy-Fired Pressurized Fluidized Bed Combustor (PFBC)**




- **Supercritical CO₂ (sCO₂) power loop key components**
 - Separate Generator and Compressor drive turbines
 - Recompression cycle with two compression and heat transfer elements

Zero Emissions Power and Steam (ZEPS™) Power Plant




- **Plant layout developed**
 - Used to estimate piping pressure losses and volumes
 - Assumed enhanced shell & tube HX technology
- **System model updated**
- **Equipment performance maps updated**
- **System Control Methodology assessed for both transient and steady state operation**

System Start




Heat Capacity



- **Variety of start-up/shutdown schemes evaluated – initially 14 valves, 4 bypass legs, & storage**
- **Detailed evaluation of two start-up approaches**
 - Spin start - concerns for thermally shocking in-bed heat exchanger
 - Motor assist bootstrap - Selected
- **Start-up requirements to mitigate damage to the system:**
 - Prevent compressor stall
 - Prevent heat exchanger overheat
 - Do not overspeed turbines
 - Avoid low Main Compressor Inlet Temperature/Pressure
- **Modified start until successful**
 - Flow split between the recycle and main compressors modified
 - LTR initially lagged thermally
 - Recirculating flow during heat up reduced
- **Final system: 6 valves, 1 bypass leg, & CO2 storage system**

System Start-Up Transient (Conventional Recuperator Technology)





System Shut Down

- **There are three shutdown scenarios envisioned:**
 - Planned Shutdown
 - Emergency Shutdown
 - Disconnect from Grid Shutdown
- **Planned shutdown**
 - Drop to 50% loaded power
 - Fuel will be cut to the unload setting - bed temperature will drop
 - Generator turbine isolation valve (V-1) will close
 - Bypass valve (V-2) will open to maintain power to the compressor turbine
 - Fuel to the PFBC will be cut and the oxygen will be switched to air
 - SCOT CO₂ flow will be circulated until appropriate bed temperatures are met before CO₂ circulation is stopped
- **Emergency shutdown and disconnect from grid are envisioned to be the same**
 - System does not have the luxury of gradually reducing heat load
 - Fuel and oxygen supply will be stopped
 - Continue bed circulation with the recycle CO₂
 - Generator turbine flow will be stopped by closing valve V-1
 - Bypass valve V-2 will be opened to a point where flow supplied to the compressor turbine is maintained
 - CO₂ temperature will decay and SCOT CO₂ flow will drop until the bed reaches a safe temperature
- **There is risk of bed overheating during Emergency shutdown, mitigations:**
 - Coal and oxygen feeds are stopped immediately
 - Water is added to the flue gas and recycle systems to offer immediate protection of the PFBC and the solids handling equipment

Operation at Partial Load

- **CO₂ mass at rated power is 229 tons**
- **Turbine inlet temp maintained at partial load**
- **Storage system required to accommodate variation in mass**
 - +6% to -2%
- **Make-up location at the inlet to the cooler**
 - Avoid impact to the main compressor
- **Drain location at the compressor outlet**
 - Pressure high and temperature low - compatible for storage



Transient Operation Analysis Conclusions

- **Two SCOT system start-up approaches were analyzed in detail and a motor assist bootstrap was selected**
 - Motor on the compressor shaft will be used to force circulation and initiate preheat of the SCOT system
- **No turbine performance issues during transient operation**
 - Normal rotordynamic and structural limits apply
- **Start-up and shutdown operation of the main and recycle compressors are within the surge, choke, and speed limits**
- **No new technology risks identified for the turbomachinery**
- **Significant transient operation benefits with compact heat exchanger designs**
- **Instrumentation and control challenges to maintain main compressor inlet near the critical point**

Acknowledgements

- The information, data or work presented herein was funded in part by Leonardo Technologies Inc, under Contract Number S163-PWR-PPM4002

Questions ?

Tony Eastland 818 586 0345


Anthony.eastland@rocket.com



Back-Up


Initial Start-Up

- The SCOT system will be pressurized once the PFBC bed temperature reaches 150°F
 - Opening valve V-5 on the CO₂ storage tank or
 - Filling from CO₂ tanker trucks using a vaporizer
- Once the system is filled, valve V-5 is closed
- Generator turbine valve (V-1) is closed
- Recycle CO₂ flow is controlled by adjusting valve V-3
- Motor on the compressor shaft will be used to force circulation and initiate preheat




System Start-Up

- Compressor turbine will quickly begin offsetting motor power
- System control to a low flow during the initial heat-up
 - Bypass more flow through valve V-2 than the compressor turbine
- Once the recuperators have reached their average temperatures and the bed has reached 1100°F, the PFBC is switched to coal firing
- The bypass valve admits more flow to the compressor turbine
- Bed heat duty continually rises and increases the flow to 50% of maximum flow.



System Start-Up (Continued)



- During ramp, the generator turbine will be preheated by slightly opening valve V-1
- Once 50% flow is reached, the generator turbine flow will be increased by further opening valve V-1
 - Synchronize with the grid

Completion of System Start-Up

- Once connected to the grid, the system will increase heat duty to the desired load
- System control will be transitioned to the turbine compressor by closing valve V-2 and throttling valve V-6
 - Completing the startup

